

25X1A

S E C R E T [REDACTED] ELEPOUCH

25X1A DISP NO - [REDACTED]

DATE - 03 DECEMBER 1968

TO

X1A INFO

FROM - [REDACTED]

25X1A SUBJECT - ENGINEERING- ADDITIONS TO [REDACTED] AIRCONDITIONING AND

POWER PLANT PROJECT

REF - A. DIRECTOR 74462

B. [REDACTED]

25X1A

C. [REDACTED]

25X1A

D. [REDACTED]

<input type="checkbox"/> E	AA
<input checked="" type="checkbox"/> ESE	DR
<input type="checkbox"/> TSE	FILE
<input type="checkbox"/> WLB	LIB
<input type="checkbox"/> [REDACTED]	FILE

68

2. IT IS RECOMMENDED THAT THE CONTRACT BE AMENDED TO INCLUDE THE FOLLOWING ITEMS AT AN ADDED COST OF APPROXIMATELY 21,500 USD:

A. THE CONTRACT SPECIFIES THAT THE CONTRACTOR IS TO FURNISH MATERIALS ONLY FOR THE AIR CONDITIONING DUCT- WORK TO BE INSTALLED IN THE CLASSIFIED AND UNCLASSIFIED .. SIGNAL CENTER AND CLANDESTINE OPERATING ROOM. STATION STAFF EMPLOYEES WERE TO HAVE MADE THESE INSTALLATIONS. IT WAS ORIGINALLY THOUGHT THAT IT WOULD BE IMPRACTICAL TO RE-LOCATE THESE FACILITIES FOR THE DURATION OF THE INSTALLATION, AND, BECAUSE OF THE SENSITIVE NATURE OF BUSINESS BEING CONDUCTED IN THE TWO OF THESE AREAS,

25X1A S E C R E T [REDACTED] PAGE 1

25X1A

S E C R E T [REDACTED] 68-1899 PAGE 2

CONTRACTOR PERSONNEL WOULD NOT BE PERMITTED ACCESS. AFTER FURTHER CONSIDERATION OF THE TIME THAT WOULD BE CONSUMED IN MAKING THE INSTALLATION, AND IN VIEW OF A REDUCTION OF ACTIVITY IN THESE AREAS, IT IS NOW APPARENT THAT EQUIPMENT RE-LOCATION IS POSSIBLE, AND THAT THE CONTRACTOR CAN DO THE JOB. HENCE, AN ESTIMATE FOR CONTRACTOR INSTALLATION IN THESE AREAS WAS REQUESTED. THE ADDITIONAL COST WAS ESTIMATED TO BE ABOUT 1,200 USD.

5X1A B. OUR NEWLY CONSTRUCTED WAREHOUSE IS WITHOUT A HARDSTAND FOR THE OUTSIDE STORAGE OF ANTENNA HARDWARE, ETC. ONE IS NEEDED TO PERMIT THE FINAL REMOVAL OF ALL STORAGE IN THE OLD [REDACTED] WAREHOUSE AREA AND TO ELIMINATE THE FIVE FN GUARDS CURRENTLY BEING RETAINED TO GUARD THAT SITE. A 40 FOOT BY 100 FOOT PAD LOCATED ADJACENT TO THE LOADING RAMP OF THE NEW WAREHOUSE AND ALONG THE EAST SIDE OF THE R-SITE COMPOUND (100FT SIDE) WOULD BE ADEQUATE. THE CONTRACTOR ESTIMATED THE ADDED COST OF A SIX INCH THICK CONCRETE PLATFORM FOR THE STAND AT 4,512 USD. IT IS IMPORTANT TO NOTE THAT SUCH A HARD-STAND, WITH VERY MINOR MODIFICATIONS, COULD BE THE FOUNDATION FOR ANOTHER PREFABRICATED STRUCTURE FOR AN ADDITIONAL WAREHOUSE, SHOULD THE NEED ARISE.

C. AN ADDITION TO THE REAR OF THE RECEIVER BUILDING, AT A COST OF 10,000 USD TO HOUSE AN INCINERATOR FACILITY AND PROVIDE A SMALL STORAGE ROOM. THE PROPOSED STRUCTURE WOULD EXTEND THE NORTH WALL OF THE RECEIVER BUILDING FROM THE NORTH EXIT DOOR TO THE NORTH EAST CORNER OF THE BUILDING BY TEN (10) FEET, THUS PROVIDING ROOM FOR TWO MODEL I INCINERATORS AND A LIMITED AMOUNT OF STORAGE. THIS ARRANGEMENT IS HIGHLY DESIREABLE SO THAT IT WOULD NOT BE NECESSARY FOR PERSONNEL TO LEAVE THE BUILDING TO BURN CLASSIFIED TRASH.

25X1A S E C R E T [REDACTED] PAGE 2

25X1A

S E C R E T [REDACTED] PAGE 3

D. AN ESTIMATE WAS ALSO REQUESTED FOR THE COST OF AN ORNAMENTAL CONCRETE HOLLOW BLOCK WALL TO SURROUND THREE SIDES OF THE ABOVE HARDSTAND TO HIDE ITS UNSIBTLY^{CH} APPEARANCE FROM VIEW. IT WOULD ALSO BE DESIRABLE TO RESTRICT THE VIEW OF THE STAND FROM THOSE INTENT ON PILFERAGE. THE COST OF THIS WALL WAS ESTIMATED TO BE 5,725 USD.

3. THE ORDER OF NEED FOR THESE CHANGES IS A THRU D. IT IS FELT¹ THAT AMPLE FUNDS ARE AVAILABLE AND [REDACTED] HAS ALREADY QUERRIED US REGARDING THE LARGE BALANCE. IT IS REQUESTED THAT WE BE ADVISED AS SOON AS POSSIBLE WHAT PARTS OF THE ^{11B}MOVE CAN BE ADDED TO THE CONTRACT.

25X1A

25X1A

[REDACTED]

TDISTRIBUTION:

[REDACTED]

25X1A